

CONCRETE BATCH PLANT



Client: Lafarge Canada Inc. – For YVR Airport Site, Richmond, B.C.

Description: Lafarge Canada required a new 150 cubic meter per hour wet batch plant to provide concrete for a large project at the airport. The project encompassed installation of a new quadra batch plant on poor bearing conditions with high settlement. The schedule from design to completion was 2 ½ months.

Scope: SDE provided foundations and innovative structural support capable of adjustment to accommodate up to 3" of settlement.